



## Factory Testing

The Casambi module in the luminaire has been factory tested to ensure communication at a distance of 10M from the fitting when no other Casambi devices or wireless networks are present.

## Site Conditions

Xero Lighting takes no responsibility for signal issues caused by site specific conditions or for the module's integration with other products and systems.

In the event there are signal issues on site the module will be tested by replicating the factory test above ie.

- All other devices and wireless networks will be switched off
- A single luminaire circuit will be energised
- Connection will be tested up to 10m from the luminaire using the Casambi app on a mobile device
- The luminaire will be considered to be functioning correctly if it can be switched on and off using the mobile device

\*The latest firmware may need to be download from the Casambi site or through the Casambi app

## System Integration

Xero Lighting does not offer support for the Casambi mobile app and takes no responsibility for its performance.

For system integration, software configuration and training, Xero Lighting recommends working with a certified Casambi commissioning partner, for example:

Afterglow Lighting  
Unit 3/12A Loyalty Road  
North Rocks NSW 2151  
+61 2 9046 9985  
info@afterglowlighting.com.au  
or for more information on the Casambi system go to: <https://casambi.com/resources/>

